

路线一路基设计表

S3-1-1

勃利县永恒乡荣光村村内水泥路工程

桩号	平曲线		坡度及竖曲线		地面 高程 (m)	设计高程 PH (m)	填挖高度 (m)		路基宽度(m)						各点与设计高PH之高差(m)						边沟及排水沟						备注	
	左	右	凹	凸			填	挖	左			右			左			中线	右			左			右			
									W2	加宽值	W1	W1	加宽值	W2	A2	加宽点	A1	AB	B1	加宽点	B2	坡度	底宽	沟底高程	坡度	底宽		沟底高程
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29
K0+000.000	R=∞ L=442.272		K0+032.915 172.520 <small>0.000, 0.000, 0.000, 0.000</small>	0.0594% 198.867 <small>40+231.782 172.638</small> <small>0.4746% 46.460</small>	172.740	172.740		0.000	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							超高旋转轴在行车道左边线
+020.000					172.600	172.623	0.023		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+040.000					172.620	172.555		0.065	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+060.000					172.570	172.536		0.034	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+080.000					172.560	172.548		0.012	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+100.000					172.550	172.560	0.010		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+120.000					172.540	172.572	0.032		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+140.000					172.530	172.584	0.054		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+160.000					172.530	172.595	0.065		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+180.000					172.620	172.607		0.013	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+200.000					172.620	172.619		0.001	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+220.000					172.630	172.630		0.000	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+240.000					172.560	172.540		0.020	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+260.000					172.320	172.329	0.009		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+280.000					172.170	172.157		0.013	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+300.000					172.160	172.174	0.014		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067							
+320.000			172.300		172.269		0.031	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+340.000			172.300		172.293		0.007	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+360.000			172.290		172.267		0.023	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+380.000			172.280		172.241		0.039	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+400.000			172.200		172.215	0.015		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+420.000			172.150		172.189	0.039		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+440.000			172.150		172.163	0.013		0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								
+442.272			172.160		172.160		0.000	0.75		2.00	2.00		0.75	-0.053		-0.030	-0.060	-0.090		-0.067								

编制:贾涛

复核: 赵胜利

审核: 任会军

审定: 张静波

路线二路基设计表

S3-1-2

勃利县永恒乡荣光村村内水泥路工程

第 2 页 共2 页

[illegible]

编制:贾涛

复核：赵胜利

审核：任会军

审定：张静波